2012 TOTAL ROADWAY RECONSTRUCTION COSTS

Construction Order	Street	Length (ft.)	Reconstruction Using Asphalt	
1	Cranbrook Drive	2,904	$	682,440
4	Huntington Drive	1,931	$	453,785
8	Coventry Drive	1,895	$	445,325
11	Cambridge Drive	1,895	$	445,325
13	Milford Drive	3,674	$	863,390
15	North Plaza Drive	3,025	$	710,875
16	Stratford Drive	842	$	197,870
17	Windsor Place	228	$	53,580
	Subtotal Plaza Subdivision		**$**	**3,852,590**
2	McKinley Drive	1,193	$	298,250
3	Lowrie Boulevard (West Section)	1,260	$	315,000
5	Monroe Drive	666	$	166,500
6	Roosevelt Drive	827	$	206,750
7	Grant Drive	341	$	85,250
9	Jefferson Drive	763	$	190,750
10	Washington Drive	1,080	$	270,000
12	Lincoln Drive	1,480	$	370,000
14	Kennedy Boulevard	2,883	$	720,750
	Subtotal Presidential Subdivision		**$**	**2,623,250**
18	Elm Street	866	$	203,510
19	Magnolia Avenue	2,613	$	614,055
20	Heights Avenue	2,550	$	599,250
21	Summit Avenue	2,475	$	518,625
	Subtotal Summit-Heights Park Subdivision		**$**	**1,935,440**

NOTE: Reconstruction of Roads Using Asphalt Include the Following: 1) Removal of Existing Asphalt Pavement, Road Subbase and Curb or Curb and Gutter, 2) 6" Aggregate Base, 3) 6" Asphalt Concrete Base, 4) 1¾" Asphalt Intermediate Course, 5) 1¼" Asphalt Surface Course, 6) Tack Coat, 7) Type 6 Curb, 8) Concrete Driveway Aprons Replacement, 9) Catch Basins Removal and Replacement, 10) Manhole Adjustments, and 11) 6"